



# Overview of the IFMIF/EVEDA Project in the Broader Approach Agreement



**Philippe Cara**


IFMIF/EVEDA Project Leader

26 March 2021

**EU S&T Counsellors**



**Target Facility**



**Accelerator Facility**



**Test Facility**

**IFMIF/EVEDA Project**



- 1 Introduction
- 2 IFMIF/EVEDA Status
- 3 LIPAc: Accelerator Facility
- 4 LIPAc: Commissioning Status
- 5 Outlook beyond 2020
- 6 Conclusions



## 1 Introduction





## IFMIF

International Fusion Materials Irradiation Facility

## EVEDA

Engineering Validation & Engineering Design Activities

Article 1.1 of Annex A of the **BA Agreement**  
mandates **IFMIF/EVEDA**

...to produce **an integrated engineering design of IFMIF** and the data necessary for future decisions on the construction, operation, exploitation and decommissioning of IFMIF, and **to validate continuous and stable operation of each IFMIF subsystem**



- Selection and qualification of candidate materials for fusion reactors
- Generation of engineering data for design, licensing and safe operation of DEMO up to end-of-life
- Completion, calibration and validation of databases (mainly generated from fission reactors research)
- Material testing and simulation carried out simultaneously to correlated fundamental understanding of radiation response of materials


**International Advisory Panels pointed out Fusion Neutron Source as essential need toward Fusion Power Plant**

**→ best fulfilled with a D-Li stripping source → IFMIF concept**



Two concurrent deuterons beam of  
125 mA CW at 40 MeV  
Impact on a liquid Li screen  
flowing at 15 m/s

Generating a footprint of 200 x 50 mm<sup>2</sup>



A flux of neutrons of  $\sim 10^{18}$  n/m<sup>2</sup>s is generated in the forward direction with a broad peak at 14 MeV and irradiate three regions:

- >20 dpa/fpy in 0.5 liters (H)
- >1 dpa/fpy in 6 liters (M)
- <1 dpa/fpy in 8 liters (L)

→ Availability of facility >70%





## 2 IFMIF/EVEDA Status



IFMIF




THE INTERNATIONAL FUSION MATERIAL  
IRRADIATION FACILITY

INTERMEDIATE ENGINEERING DESIGN REPORT



The IFMIF EDA Long-term Project Team

## Engineering Design Activities – EDA phase Successfully delivered on schedule


### Validation Activities – EVA phase







**D<sup>+</sup> Accelerator**  
incident current 125 mA




**Lithium jet at 250 C**  
**Flow speed 15 m/s**  
**Thickness  $25 \pm 1$  mm**



## Milestones

**Construction completed** on 19 Nov. 2010



**Test completed** on 31 March 2015



## Results:


No change in Li target thickness and stable Li target throughout the continuous operation for 571 h (~24 days).

**System Integration was successfully demonstrated**  
**March 2015**



**Engineering Validation Activities** completed on Feb. 2017







6 reference specimens have been developed

Specimen type	Geometry
Tensile	
Fatigue	
Bend/Charpy DFT	
Creep	
Crack growth	
Fracture toughness	




Fatigue A

Bundle-2 Bundle-1 Alloy A



Alloy B

Fatigue B




Successfully tested  
using the Belgian  
material test reactor  
BR2 in Mol



## IFMIF TEST MODULES



HFTM-DC  
in Karlsruhe




**Validation Activities completed on Apr. 2015**




IFMIF

LIPAc




Small but challenging






EDA phase:




EVA phase:



Test Facility



Target Facility



**LIPAc (Linear IFMIF Prototype Accelerator) – Accelerator Facility**  
**9MeV, 125mA CW, 1.125 MW**






3

LIPAc: Accelerator Facility



## Japan-Europe scientific collaboration



Equipment designed and constructed in Europe, Installed and commissioned in Rokkasho




World's highest current linac in  $H^+$  and  $D^+$  in CW

World's top  $H^+$  &  $D^+$  injector performance

World's longest RFQ

World's record of light hadrons current through SC cavities

World's highest beam perveance





**Project Coordinated by**  
**IFMIF/EVEDA Project Leader**  
 In liaison with 2 Home Teams



**Organization evolved since 2007....**

**LIPAc Organization Since 2018:**

- Beam Operation,
- Maintenance,
- Installation & Commissioning...


**System Installation, Checkout, Start-up, Commissioning**

*LIPAc Unit in Rokkasho*

**~50 people**



LIPAc Operation Team



IFMIF/EVEDA CQMS-0920 (DMS Ref. BA\_D\_27MTRJ)







4

LIPAc: Commissioning Status



**4 configurations considered for 5 commissioning phases to validate the LIPAc performances**



## 1<sup>st</sup> configuration – Commissioning Phase A

Phase A  
**100 keV - 125 mA**  
 12.5 kW



Injector

CW

Diagnostic Box + Beamstop





(Apr.2015 - Aug.2017)

COMPLETED



## LIPAc injector requirements

- D<sup>+</sup> beam.
- Energy: **100 keV**.
- Intensity: **140 mA**.
- Final emittance:  $\leq 0.3 \pi$  mm.mrad (**target value:  $\leq 0.25 \pi$  mm.mrad**).
- Twiss parameters at the RFQ entrance: less than 10% mismatch





## 2<sup>nd</sup> configuration – Commissioning Phase B



Phase B  
5 MeV - 125 mA  
625 kW – low DC

Injector

CW

Diagnostic Box + Beamstop

(Apr.2015 - Aug.2017)

Injector

RFQ + MEBT

D-Plate+BD

0.1-1ms


(June 2018 – August 2019)

Diag.-Plate + Low Power Beam Dump

COMPLETED



*Phase B installation was completed in October 2017.*



*Operation Mode  
2 shifts  
Beam Operation  
&  
RFQ Conditioning*






## Achieved in LIPAc research activity

- RF operation at full RF level (**132 kV**)
- Beam acceleration with nominal space charge with pulsed:
  - Proton beam (**2.5 MeV, 60mA**)
  - Deuteron beam acceleration (**5 MeV, 125 mA**)

*Celebration of the end of 5 MeV, 125 mA, D+ beam acceleration on 9<sup>th</sup> Aug 2019*



**We demonstrate that all the components needed to run the LIPAc accelerator in the phase B configuration work as expected.**




> 90% Beam transmission through the RFQ

Significant project milestone reached  
(125 mA, @ 5 MeV, 1 ms pulse)



## 3<sup>rd</sup> configuration – Commissioning Phase B+



Injector

CW

Diagnostic Box + Beam stop

(Apr.2015 - Aug.2017)

Injector

RFQ + MEBT

D-Plate+BD

0.1-1ms

(June 2018 – August 2019)

Diag.-Plate + Low Power Beam Dump

Injector

RFQ + MEBT

Drift line + HEBT/D-Plate


1ms-CW

Final Beam Dump




## Phase B+: LIPAc in temporary configuration

**5 MeV - 125 mA**  
**625 kW – high DC**



## Phase C/D: LIPAc in its final configuration

**9 MeV - 125 mA**  
**1.125 MW – low and high DC**





Check-out tests and individual commissioning of the  
HEBT/BD on going  
(Performed remotely)

Injector and RF injection started

Start Beam Operation by the end of second trimester



LIPAc construction for phase B+



Beam Dump



Injector

RFQ

MEBT

MEBT Extension Line

HEBT

D-plate

Beam dump


LIPAc construction completed for phase B+



## 4<sup>th</sup> configuration – Commissioning Phase C/D

**Phase C (installation SRF Linac)**  
**9 MeV - 125 mA**  
**1.125 MW – low DC**

**Phase D**  
**9 MeV - 125 mA**  
**1.125 MW – low to high DC**



FINAL STAGE

**Injector** **CW** Diagnostic Box + Beam stop  
 (Apr.2015 - Aug.2017)

**Injector** **RFQ + MEBT** **D-Plate+BD** **0.1-1ms**  
 (June 2018 – August 2019) Diag.-Plate + Low Power Beam Dump



**Injector** **RFQ + MEBT** **Drift line + HEBT/D-Plate** **1ms-CW** Final Beam Dump

**Injector** **RFQ + MEBT** **SRFL + HEBT/D-Plate** **1 ms/CW** Final Beam Dump



## Components under assembly in Rokkasho

- ☑ A clean room has been built in Rokkasho under the responsibility of QST in the DEMO Joint Research Building
- ☑ F4E is responsible of the assembly, CEA provide support
- ☑ Almost all components delivered on site, assembly to start last semester 2021







## 5 Outlook beyond 2020



In March 2020, Euratom and Japan signed a joint declaration reaffirming their collaboration via the Broader Approach agreement

For IFMIF/EVEDA this fruitful collaboration is continuing in pursuing the mandate assigned to IFMIF/EVEDA Project by:

- ✓ Complementing the engineering design of the IFMIF-like Fusion Neutron Source and complementing the Lithium Target Facility engineering validation,
- ✓ Continuing the commissioning of the LIPAc (Phase B+, C and D), by enhancing systems already validated during the first phases.



- ❑ **2020-2022: Phase B+ commissioning (125 mA D+, 5 MeV – High Duty cycle)**
- ❑ **2021-2022: Assembly, integration and checkout tests of the cryomodule**
- ❑ **2023-2024: Phase C/D Commissioning (125 mA D+, 9 MeV – CW)**
- ❑ **2021-2025: LIPAc enhancement activities to improve both reliability and availability required for the fusion neutron source (e.g. A-FNS/DONES), but also to validate the operation requirements**



**The Fusion Neutron Source engineering design activities and the Lithium Target Facility engineering validation activities have restarted in 2020 aiming to provide an updated Fusion Neutron Source Engineering Design report.**

**The main activities will be dedicated to:**

- ☐ **The enhancement of the design of the Lithium loop (e.g. tritium migration, erosion/deposition modelling, purification, accident analysis, optimization of the Li-Oil Heat Exchanger),**
- ☐ **The update of the Fusion Neutron Source Design focusing in the design activities for safety and accidental analyses.**





6

## Conclusions



- Since the project started in 2007, this international collaboration continues to grow and has achieved important milestones,
- We have managed to create an excellent team spirit with the ‘in-kind’ suppliers, F4E and QST,
- The recent progress and achievements reflect the importance of the fruitful collaboration between Japan and Europe for the development of the future fusion neutron source by:
  - ❑ Completing the design activities for the future neutron sources,
  - ❑ Enhancing the systems to demonstrate the full reliability,
  - ❑ Maintaining the competences and already developed know-how that are essential for the future.



# Thank you for your attention!



*Celebration of 5 MeV, 125 mA, D<sup>+</sup> beam acceleration  
9<sup>th</sup> Aug 2019*

